Last Mile Solutions

Certified Charge Point List

Vendor	Model	Certified	Certification Date	Controller	Vendor (EVC-net)	Model (EVC-net)	OCPP Connection	Security Profile	Communication Protocol	Tested with	Tested Firmware Version	Upload FW LMS	Charger Type	Connectors	MID Meter	Eichrecht Compliant	Charging Profiles Capable	Smart Charging	Edge Compliant	Payment Terminal	Comments	Setup Instructions
ABB	MD_TERRA_53_54	Certified	July 5, 2019		abb	md_terra_53_54	Proxy Connection	0	OCPP JSON 1.6	SIM	4.0.3.47	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
ABB	TERRA T94/T124/T184	Certified	August 31, 2023		abb	terra_t94_t124_t184	Proxy Connection	0	OCPP JSON 1.6	SIM, LAN	1.7.3.39	No	DC	CCS2 Cable	Yes	Not tested	Yes	Yes	Yes	Yes	Eichrecht test missing	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
ABB	TERRA 360	Certified	February 15, 2022		abb	terra_360	Proxy Connection	0	OCPP JSON 1.6	SIM, LAN	0.1.0.75	No	DC	CCS2 Cable	Yes	Not tested	Yes	Yes	Yes	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
ABB	Terra AC	Approved (Limited)	March 15, 2021		abb	terra_ac_limited	Proxy Connection	0	OCPP JSON 1.6	SIM	V1.6.5	No	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested	GetDiagnostics issue	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ABL	3W2215 and 3W2263 (eMH3)	Certified	December 6, 2022		abl	emh3	Direct connection	0	OCPP JSON 1.6	SIM	1.5p3 and 1.8p2	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ABL	eM4 (100000xxx)	Certified	October 23, 2023		abl	em4	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.0p4	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Transactions can only be stopped by the car	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ABL	eMC3	Certified	July 29, 2025		abl	emc3	Direct connection	0	OCPP JSON 1.6	SIM	1.8p4	Yes	AC	T2 Socket	Yes	Yes	Not tested	Not tested	Not tested	Not tested	Charger Unavailable-- Charger lights remain green.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ads-tec Energy GmbH	CHARGE POST	Certified	June 16, 2026		ads_tec	charge_post	Direct connection	0+2	OCPP JSON 1.6	SIM, LAN	1.2.0 1.11.1	Not supported	DC	CCS2 Cable	Yes	Yes	No	No	No	Not tested	Firmware updates and diagnostics are only available through the manufacturer.	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
AgroCharge	JY2	Certified	January 23, 2025	IOC	agrocharge	jy2	Direct connection	2	OCPP JSON 1.6	SIM, LAN	24082401-24071501	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
AKLoad	Phoenix series	Certified	September 12, 2022	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.2.0	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Alfen BV	AHP-Series: Eve Single Plus Eve Double Plus Twin4XL V2G Twin 5 Twin 5 Plus	Certified	May 2, 2025		alfen	ahp_series	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	2.1.0-RC2 2.4.0 2.5.0	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Alfen BV	Compact (before 2017) Twin 3.0, 4.0, 4.2 (before 2017) EVe-dual (before 2017)	Certified	Unknown		alfen	advanced_series	Direct connection	0	OCPP JSON 1.5	SIM, LAN	No data availible	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Alfen BV	NG (Next Generation): Eve Single S-line (NG910) Eve Single Pro-line (NG910) Eve Double Pro-line (NG920) Twin4XL (NG920)	Certified	September 15, 2026		alfen	ng9xx_series	Direct connection	0	OCPP JSON 1.6	SIM, LAN	4.11.0-3266 4.15.6-4040 4.15.6-4041 6.6.2-4312 6.6.2-4351 6.6.2-4396 7.0.2-4322 7.0.5-4328 7.1.6-4345 7.3.0-4411 7.4.0-4401 Not advised 7.4.2-4405 Not advised 7.4.4 7.4.5 7.4.6	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested	If fitted with a screen and Firmware version 6.6 available, this charger can display a QR code to start a remote charging session compliant with AFIR. Find setup instructions in our knowledge base.	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/alfen-enable-qr-code-for-direct-payment-afir-compliant/
Alfen BV	Lolo 3 (Only LAN)	Certified	December 21, 2021		alfen	lolo_3	Direct connection	0	OCPP JSON 1.5	SIM, LAN	4.15.6-4038	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Alpitronic	HYC1000	Certified	July 31, 2026		alpitronic	hyc1000	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	v3.1.0	Not Tested	DC	T2combo ,MCS	Yes	Yes	Yes	No	Yes	Not tested	This charger has 2 dispensers, and each dispenser has 2 outlets. The CPO needs to create 2 charger profiles in Last Mile Solutions in order to support both connections.	
Alpitronic GmbH	HYC200/400	Approved (Limited)	December 17, 2024		alpitronic	hyc200_400_limited	Direct connection	0	OCPP JSON 1.6	SIM, LAN	hyc_v2.3.0-RC8	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Yes	Issue with StopTransaction in case of power loss.	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Alpitronic GmbH	HYC50/150/300	Certified	June 12, 2022		alpitronic	hyc50_150_300	Direct connection	0	OCPP JSON 1.6	SIM, LAN	Hyc_v1.6.5	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Amina Charging	c1	Approved (Limited)	May 28, 2026		amina	c1	Direct connection	0	OCPP JSON 1.6	E-SIM	0.0.0+C4.2.105+P1.107.62	No	AC	CCS2 Cable	No	No	Yes	No	Yes	No	GetDiagnostics issue	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Amperfied GmbH	Connect.Public	Certified	September 8, 2023	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	LAN	5.21.2-13536	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ANYOS	ANY M	Certified	April 8, 2024		anyos	any_m	Direct connection	0	OCPP JSON 1.6	LAN	v3.5.3-3	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ANYOS	ANY S	Certified	February 27, 2024		anyos	any_s	Direct connection	0	OCPP JSON 1.6	LAN	V3.5.2	Not Tested	AC	T2 Socket	Yes	No	Yes	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Arex wbgroup.pl	ECS-01W	Certified	December 10, 2024		arex	ecs_01w	Direct connection	0	OCPP JSON 1.6	SIM, LAN	0.0.4	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Arex wbgroup.pl	DCX-1 and DCX-2	Approved (Limited)	April 13, 2026		arex	dcx_n	Direct connection	2	OCPP JSON 1.6	Pub SIM, LAN	2.1.48	No	DC	CCS2 Cable	Yes	No	Not tested	Not tested	Not tested	Not tested	Only use this with a public connection. This allows the manufacturer to access the charger's diagnostics when needed and perform firmware updates.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Autel Europe	MaxiChargerDC/DC Compact 47kW	Certified	October 10, 2022		autel	maxicharger_dc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	CP	Not Tested	DC	CCS2 Cable	Yes	No	No	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Autel Europe	MaxiCharger AC LAN	Certified	January 26, 2023		autel	maxicharger_ac	Direct connection	0	OCPP JSON 1.6	SIM, LAN	CARo1PAQYA	No	AC	T2 Socket	Yes	No	No	Unknown	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Autel Europe	MaxiCharger AC Ultra	Certified	November 19, 2025		autel	maxicharger_ac_ultra	Direct connection	0	OCPP JSON 1.6	SIM, LAN	PFA0001|1.00.00|1.32.00|1.21.00|2.41.00|1.01.00	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Awesems Nederland	ProMax 22/44 /ProMax 63	Certified	September 27, 2024	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	Public SIM	5.33.1-20092	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Bender Controller	CC613	Certified	February 3, 2022	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.20.3-13066	No	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
BENY New Energy	BDC240-DC BDCx-S, BDCx-D, BDCx-T, BDCx-F, BADCx-S BADCx-D, BVDC22, BBDCx, BBDCx-D, BGDCx-D, BLDCx-D, BMDCx-D, BDDCx-D, BDESC-8040, BSDCx, BODCx-S, BODCx-D	Certified	December 5, 2025		beny	bdc240_dc	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	1.1.14	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
BENY New Energy	BCP-AT2 SocketN-P	Certified	June 20, 2024		beny	bcp_a	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.0.34	Not Tested	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Blue Current	U-MOVE22/HIDDEN/ NANO(XL)	Certified	May 3, 2024		blue_current	u_move22	Proxy Connection	0	OCPP JSON 1.6	LAN	0.2.2-patch.range.values.and.defaults+dirty.191d36	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
BorgWarner	HPCi	Certified	February 3, 2025	Vector vSECC	borg_warner	hpci	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.3.1	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Cahors	WA-PP-22kW-T2 SocketS+EF	Certified	June 18, 2025		cahors	wa_pp	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	B120-1.91	Yes	AC	T2 Socket	Optional	No	Yes	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Rheinmetall	Ladebordstein (Bender controller)	Certified	November 9, 2026	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.34.4-21648	Yes	AC	T2 Socket	Yes	Yes	Yes	Yes	Yes	No		
Sicon Chat Union Electric	MBS241	Approved (Limited)	November 10, 2026		sicon	mbs241_limited	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	1.5.0	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	1.BootNotification is missing vendor and model data 2.StopTransaction possible without any authorisation.	
Cenenergy	Arca, DUO, Stila-C/S (BENDER CONTROLLER)	Certified	September 11, 2026	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.34.0-21361	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Yes	No		
Cenenergy	EasyHybrid	Certified	Unknown	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM, LAN	Unknown	No	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Cenenergy	Arca	Certified	Unknown	EVC4.22	LMS	V4.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM, LAN	Unknown	Yes	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Cenenergy	Domia	Certified	Unknown	EVC4.22	LMS	V4.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM, LAN	Unknown	Yes	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Cenenergy	Duo	Certified	Unknown	EVC4.22	LMS	V4.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM, LAN	Unknown	Yes	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Cenenergy	Stila	Certified	Unknown	EVC4.22	LMS	V4.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM, LAN	Unknown	Yes	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Chago	EVC200 and EVF200	Certified	August 1, 2019		chago	evc_evf_200	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.10-7027	Yes	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Charge Amps	Aura/Halo	Certified	November 3, 2022		chargeamps	aura_halo	Proxy Connection	0	OCPP JSON 1.6	LAN	66.2.0.0	No	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Charge Amps	DAWN	Certified	November 16, 2023		chargeamps	dawn	Proxy Connection	0	OCPP JSON 1.6	SIM, LAN	1.3.1	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Chargepoint Europe	Neon Premium/Cobalt/Platinum	Certified	August 14, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.2.0	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Chargepoint Europe	Neon	Certified	August 7, 2026	Prodrive	chargepoint	neon	Direct connection	2	OCPP JSON 1.6	SIM	1.9.2 1.9.1 1.9.0 1.8.1 1.8.0 1.1.1+1+CHARGEPOINT-2	No	AC	T2 Socket	Yes	Not tested	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
chengdu_honors_technology	3p_40k_d1_80a_eu01	Certified	November 28, 2025		chengdu_honors_technology	3p_40k_d1_80a_eu01	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	4.1.0;106.25.110.4;6.25.110.4	Yes	DC	T2 Cable	Yes	Not tested	Yes	Yes	Yes	Not tested	This is a potable mobile DC charger	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Circontrol	Controller A8(DC Raption, (AC eVolve and DC eVolve Rapid) Master) Series	Certified	April 26, 2022		circontrol	a8	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.3.0-rc2	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Circontrol	Controller ccl1-mini (WB Smart, eNext Park, WbB/Post eVolve PT3) Series	Certified	December 10, 2018		circontrol	ccl1mini	Direct connection	0	OCPP JSON 1.6	SIM, LAN	ccl13.2.0-rc1	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Circontrol	Controller Variscite enext (eNext Elite)	Certified	February 23, 2023		circontrol	enext	Direct connection	0	OCPP JSON 1.6	LAN	ccl2 1.0.0-rc5	Not Tested	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Circontrol	Controller Variscite ccl2 (eVolve Smart T)	Certified	February 23, 2023		circontrol	ccl2	Direct connection	0	OCPP JSON 1.6	LAN	ccl2 1.0.0-rc5	Not Tested	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Coolblue	BlueBuilt_WLAC1	Certified	May 8, 2026	Prodrive	coolblue	bluebuilt_wlac1	Proxy Connection	2	OCPP JSON 1.6	SIM	1.6.1+1+COOLBLUE-1	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
CTEK E-Mobility AB	CS Connected v2	Certified	February 14, 2023		ctek	csconnected2	Direct connection	0	OCPP JSON 1.6	SIM, LAN	ccu_R3.11.18.2-0	Yes	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Daze Technology	DS02M/US01M	Certified	March 24, 2025		daze	ds02m	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	2.2.1.1.1.5	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Charger doesn't support LMS vpn sim cards rather to be used are public sim cards, Wifi or Ethernet.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
DBT-CEV	NQC-ACDC-COMBO	Certified	February 25, 2019		dbt	nqc	Direct connection	0	OCPP JSON 1.6		1.3.28	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
DBT-CEV	L2/Keren	Certified	October 4, 2019		dbt	l2	Direct connection	0	OCPP SOAP 1.5	Lan	Qcng_firmware-Rls-1.1.0.0	No	AC/DC	CCS2 Cable T2 Socket/Cable	No	No	No	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Delta Electronics	Model 10566	Certified	December 22, 2018		delta	10566	Direct connection	0	OCPP JSON 1.6	SIM	3.2rc7	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	No	No	Yes	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Delta Electronics	UFC/SLIM/DCWB Models	Certified	September 24, 2025		delta	ufc_slim	Direct connection	0	OCPP JSON 1.6	SIM	4.2.1 and 3.6.3	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	Not tested	Yes	Yes	Yes	Yes	Echirecht not tested yet.	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
DiniTech GmbH	NRGkick	Certified	September 27, 2024		dini_tech	nrgkick	Proxy Connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	SM:4.0.0.100/MC:3.1.4.5	Not Tested	AC	T2 Socket	No	No	No	No	Not tested	Not tested	Open transactions are automatically closed at the end of the month.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Easee	Charge MAX and Pro	Certified	September 8, 2025		easee	charge_max_pro	Proxy Connection	0	OCPP JSON 1.6	WIFI	330/1.7.5.0	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Test: StopTransaction – Power LossResult: ✕ Failed – No data, timestamp = 1970-01-01T00:00:25Z	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Easee	Easee Home/charge/Lite robot	Certified	September 16, 2022		easee	home_charge_lite_robot	Proxy Connection	0	OCPP JSON 1.6	LAN	296/1.6.0.0	No	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Easycharger (New South Technology)	DC(S03M, S03MD, S05P, S05H)	Certified	June 30, 2026		easycharger	dc_s03_s05	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V30.57_T6 DC_V30.66_0602	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Easycharger (New South Technology)	AC-EV44K-X3 (S08W)	Approved (Limited)	September 23, 2025		easycharger	ac_ev44k_x3_limited	Direct connection	0	OCPP JSON 1.6	SIM	ACM4_EVC_V1.33.3	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Double transaction after soft reset.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Eaton Green Motion	DC 22 44 66	Certified	August 22, 2024		eaton_green_motion	dc224466	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2003	Not Tested	DC	CCS2 Cable	No	No	No	Yes	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Eaton Green Motion	Omnibox	Certified	May 28, 2024		eaton_green_motion	omnibox	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1807	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	No sim info in the boot	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EBG Compleo GmbH /Innogy	Ebox Professional S	Certified	October 16, 2023		compleo	ebox_professional	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.3.29 2.1.0	Yes	AC	T2 Socket	No	No	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EBG Compleo GmbH	Cito240	Certified	Unknown		compleo	cito240	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Not Tested	DC	CCS2 Cable	Yes	Yes	Not tested	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EBG Compleo GmbH	Cito500	Certified	May 26, 2023		compleo	Cito500	Direct connection	0	OCPP JSON 1.6	SIM	5.19.4-500	No	DC	CCS2 Cable	Yes	Yes	Yes	Yes	Not tested	Not tested	PTB certification in progress	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EBG Compleo GmbH	DUO (ims) /Fleet	Certified	May 2, 2022		compleo	solo_duo_advanced	Direct connection	0	OCPP JSON 1.6	SIM	5.18.12	Not Tested	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EBG Compleo GmbH	Solo CS AG /Advanced P4	Certified	March 21, 2022		compleo	solo_duo_advanced	Direct connection	0	OCPP JSON 1.6	SIM	6.2.2	Yes	AC	T2 Socket	Yes	Yes	Not tested	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
eCharge Hardy Barth	cPH1 1T2 Socket2/cPP1 2T44	Certified	November 6, 2018		echarge_hardy_barth	cph1_cpp1	Direct connection	0	OCPP JSON 1.6	SIM	78000001 0.51 V1.24	Unknown	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
eCharge Hardy Barth	cPH2/cPP2 1T2 Socket2	Certified	September 14, 2023		echarge_hardy_barth	cph2_cpp2	Direct connection	0	OCPP JSON 1.6	SIM	1.87.0	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
eCharge Hardy Barth	cPH2/cPP2 1T2 Socket2 Eichrecht	Certified	September 29, 2023		echarge_hardy_barth	cph2_cpp2_eichr	Direct connection	0	OCPP JSON 1.6	LAN	2.94.0	Not Tested	AC	T2 Socket	Yes	Yes	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ecotap	Ecotap Duo Wide	Certified	March 18, 2025	EVC 5.2 AC	Ecotap	EVC 5.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM	32R35	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ecotap	DUO 3X63A	Certified	January 4, 2019	EVC4.22	ecotap	DUO 3X63A	Direct connection	0	LMS & OCPP JSON 1.6	SIM	V1.14.0	Yes	AC	T2 Socket	Yes	Yes	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ecotap	Homebox 3X16(32)A /SOLO 3x32A	Approved (Limited)	August 15, 2023	EVC4.22	ecotap	Homebox 3X16A/3X32A/1X16A//SOLO 3x32	Direct connection	0	LMS & OCPP JSON 1.6	SIM	32R.16	Not Tested	AC	T2 Socket	Yes	Not tested	Yes	Yes	Not tested	Not tested	GetDiagnostics does not work for OCPP 1.6.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ecotap	AC_22.0KW	Certified	November 7, 2022	EVC5.06	Ecotap	EVC 5.2	Direct connection	0	LMS & OCPP JSON 1.6	SIM	506.32R.27	Yes	AC	T2 Socket	Yes	Yes	Not tested	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ecotap	DC-15	Certified	Unknown				Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Yes	DC	CCS2 Cable	Optional	Yes	Yes	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Efacec	HV350 , HV Standard	Certified	December 14, 2022		efacec	hv_standard	Direct connection	0	OCPP JSON 1.6	SIM	HV_N_MSC64_1.6w_7.3.14_4_full	No	DC	CCS2 Cable	Yes	No	No	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Efacec	QC45	Certified	Before 5/15/2019		efacec	qc45	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Unknown	AC/DC	CCS2 Cable T2 Socket/Cable	No	No	Not tested	Unknown	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Ejoin	RC-F2.40.6-ALEX.A000	Certified	September 23, 2025		ejoin	rc_f2_40	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	SC.2509.1260	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Not tested	models thats use the same firmware include RC- Rapid charge,RB- Rapid Box,RM -Rapid Move,RT- Rapid Terminal,RP-Rapid Pole	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ekoenergetyka	AxonFX	Certified	October 31, 2022		ekoenergetyka	axon_sat_series	Direct connection	0	OCPP JSON 1.6	SIM, LAN	i1.12.0u2.10.3m0.4.3o4.8	Yes	DC	CCS2 Cable	Yes	Yes	Yes	Unknown	Not tested	Yes	CCV payment terminal Eichrechtt compliant chargers: AXE-A530T1010H-9016 AXE-B230T1010H-9016 AXE-B830T1010H-9016 AXE-B860T1010H-9016 catalogue codes	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Ekoenergetyka	AxonFX,AxonSide, SAT400,SAT600	Certified	October 15, 2024		ekoenergetyka	axon_sat_series	Direct connection	0	OCPP JSON 1.6	SIM, LAN	leko 0.36.0-r0	Yes	DC	CCS2 Cable	Yes	Yes	Yes	Yes	Yes	Yes	CCV payment terminal Eichrechtt compliant chargers: AXE-A530T1010H-9016 AXE-B230T1010H-9016 AXE-B830T1010H-9016 AXE-B860T1010H-9016 catalogue codes	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
ElectroAir	EACharger DC	Certified	August 21, 2024		electroair	ea_charger_dc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	EACH_ACDC_240731_01	No	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Elinta	CityChargeV2 CityChargeMini2 HomeBox Slim	Certified	August 5, 2022		elinta_charge	citychargev2_citychargemini2_homebox_slim	Proxy Connection	0	OCPP JSON 1.6	LAN	HW v60, SW v72	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Connection via Elinta cloud, remote dignostics and firmware update provided by Elinta directly	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ELLI	Flexpole	Certified	December 10, 2024		elli	flexpole	Direct connection	0	OCPP JSON 1.6	SIM, LAN	SW 4.1.2.6	Yes	DC	CCS2 Cable	Yes	Yes	No	Yes	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Elzab	ECOPOWER CC Wall	Certified	March 20, 2024	Bender	elzab	ecopowercc_wall	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.29.2	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Emiter	ZEVS	Certified	April 2, 2024		emiter	zevs	Direct connection	0	OCPP JSON 1.6	SIM, LAN	0.2.1490	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EN+	ARGO	Certified	August 19, 2025		en+	argo	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	V1.7.933	Not Tested	AC	T2 Socket	No	No	Yes	Yes	No	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EN+	CARO-C011K-BE-35 (48/49/50/51)	Certified	October 24, 2024		en+	caro	Direct connection	0	OCPP JSON 1.6	LAN	1.0.23.248	Not Tested	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EN+	VITA-AC022K-BE- 34-WPBKS-WE (187/145/132/185)	Certified	July 31, 2024		en+	vita	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	V1.5.673	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Eneco	Connectric	Certified	August 14, 2023	Prodrive	eneco	connectric	Direct connection	2	OCPP JSON 1.6	SIM	1.1.1+1+CHARGEPOINT-2	No	AC	T2 Socket	Yes	Not tested	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enelion	Com2.4	Certified	September 24, 2018		enelion	com2_4	Direct connection	0	OCPP JSON 1.6	SIM	1.2.2	Yes	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enelion	Lumina	Certified	June 16, 2025		enelion	lumina	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	2.9.1	No	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	tested with only public sim	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enelion	Vertica (Bridge2.6Q)	Certified	June 16, 2025		enelion	vertica	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	4.5.0	No	AC	T2 Socket	Optional	No	Yes	Yes	Yes	Not tested	tested with only public sim	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EnerCharge	ECC320, ECC500,AE102, AE103, AE104 AE106, AE107, AE108, AE109 AE10D, AE10E, AE10F, AE10G AE10H, AE10L, AE10J, AE10K AE10M, AE110, AE111, AE105	Certified	24-Jul-2023		enercharge	ecc320_500	Direct connection	0	OCPP JSON 1.6	SIM	1.1.3.31	No	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Enovates	Curved Pro BC1770P(E)	Approved (Limited)	April 30, 2026		enovates	curved_limited	Direct connection	1	OCPP JSON 1.6	Lan	70.15.0 256a3b3	No	AC	T2 Socket	No	No	No	No	No	No	Charger does not support diagnostics Meter values do not include the required data to display power and energy in the real-time dashboard	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enovates	Chargewell Gen22	Certified	February 17, 2023		enovates	gen22	Direct connection	0	OCPP JSON 1.6	SIM	1.13.1.3@ 118.1.1 and 2.4.1.18	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enovates	chargepoint_p5	Certified	Unknown		enovates	chargepoint_p5	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Unknown	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enovates	PRO22 /PRO44	Certified	April 28, 2025		enovates	pro22_pro44	Direct connection	0	OCPP JSON 1.6	SIM	1.7.0+1+SHELL-1	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enovates	PRO400 and ENO public serie	Certified	September 1, 2025		enovates	pro400	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.14.1.7@ 3.2.5.1.3293 and 3.2.5.1	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Enphase	IQ-EVSE-EU-3032-0105/0005	Certified	April 23, 2026		enphase	iq_ev_charger_2	Proxy Connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	26.5.1.9	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Charger has a proxy connection and diagnostics from the charger can be provided by team Enphase.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ensto/Chago	EVB200	Certified	May 5, 2023	Bender	ensto	evb200	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.29.3-13498	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Entratek	Power Dot Fix(Iocharger) Power Arrow Dual (IOCAP06C) Power Dot Mini (IOCAH30)	Certified	October 21, 2024		iocharger	ioc	Direct connection	2	OCPP JSON 1.6	SIM	21121901-21111301-21111301	Not Tested	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ep_energy	EPCS209	Certified	April 30, 2026		ep_energy	epcs209	Direct connection	2	OCPP JSON 1.6	SIM, WIFI,LAN	T8.24.6-C4.0.5-S.A0.0.0.0-S.B0.0.0.0	Not Tested	DC	T2 Cable	Yes	No	Yes	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
E-RS/Atechnics	Raepsaet/ EVD_B_NFC	Certified	April 24, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.2.0	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.

eSystems (Elli)	ESYSTEMS_AC02_CONNECT_11 (22) ESYSTEMS_AC02_PRO_22 (EICHRECHT)	Certified	July 3, 2026		esystems	ac02	Direct connection	0+2	OCPP JSON 1.6	LAN	R04.004.046.011-elli	Yes	AC	T2 Socket	Yes	Yes	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
eSystems (Kontron)	Steca and Volvo models	Certified	August 18, 2026		esystems	steca_volvo	Direct connection	0+2	OCPP JSON 1.6	SIM, LAN	R04.004.046.012-ghostone	Yes	AC	T2 Socket	Optional	Yes	Yes	Yes	Yes	Yes	Not tested		
ETEK	EVS-TYPE2-07	Certified	June 24, 2025	ekepc3	etek	ekepc3	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	AC_V2.3.25	No	AC	T2 Socket	Yes	No	Yes	No	No	No	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
E-Totem	eCity	Certified	September 8, 2022		e_totem	e_city_e_premium	Direct connection	0	OCPP JSON 1.6	SIM	3.18a-rc23-tcp	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
E-Totem	ePremium eDuty / eFast_250	Certified	November 8, 2024		e_totem	e_premium_e_duty_efast_250	Direct connection	0	OCPP JSON 1.6	SIM	3.18a-rc38-tcp-ng|v6.06	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	No	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
E-Totem	ePremium/eSmart	Certified	April 4, 2024		e_totem	e_premium_e_smart	Direct connection	0	OCPP JSON 1.6	SIM	3.18a-rc38-tcp-ng|v6.06	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Etrel	INCH Home (G-HC1Z7BY10)	Approved (Limited)	November 25, 2025		etrel	inch_home_limited	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	6.0:6.0	Not Tested	AC	T2 Socket	Unknown	No	Yes	Yes	Yes	Yes	Not tested	GetDiagnostics - failed and simcards are not mandetory for the home chargers	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Etrel	INCH Pro G-PC1V5BY40 G-PC1Z5BY10 G-PC1SBDY40	Certified	May 23, 2023		etrel	inch_pro	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.0.1, 6.0:6.0	Not Tested	AC	T2 Socket	Unknown	No	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Euroloop	Amber1	Certified	September 1, 2023		euroloop	amber1	Direct connection	0	OCPP JSON 1.6	SIM	diverged rfid new 00be67b0	No	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested	Not tested	SIM card delivered and maintained by charger suppli	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EV VOLTA	187	Certified	September 19, 2024		ev_volta	187	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.5.673	Not Tested	AC	T2 Socket	Yes	No	Yes	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EV VOLTA	Smart City	Certified	March 18, 2024		ev_volta	smart_city	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.5.0 and 1.6.3	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	terminal tested with Ingenico Self 2000 terminal	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EVBox	UltronIQ	Certified	December 9, 2021		evbox	ultroniq	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.1.3	Not Tested	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested	Not tested	Eichrecht test August 2023	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EVBox	G2-HomeLine/BusinessLine	Certified	Unknown		evbox	g2_homeline_businessline	Direct connection	0	OCPP JSON 1.6	SIM, LAN	Unknown	Not Tested	AC	T2 Socket	Optional	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVBox	G3-BusinessLine	Certified	April 3, 2019		evbox	g3_businessline	Direct connection	0	OCPP JSON 1.6	SIM	P0134B0122v0.190313	Yes	AC	T2 Socket	Optional	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVBox	G4-BusinessLine/Elvi	Certified	August 13, 2019		evbox	g4_businessline_elvi	Direct connection	0	OCPP JSON 1.6	SIM, LAN	P0414B0414v2.190517_U6.0.0-050	Yes	AC	T2 Socket	Optional	Yes	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVBox	Livo	Approved (Limited)	February 12, 2024		evbox	livo_liviqo_limited	Direct connection	0	OCPP 2.01	SIM	v5.20.5-rc7;v1.27.4	No	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested	GetDiagnostis issue	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVBox	SPS OCPP SOAP	Certified	Unknown		evbox	sps	Direct connection	0	OCPP SOAP 1.6	SIM, LAN	Unknown	Not Tested	AC	T2 Socket	Unknown	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVBox	Troniq 50	Certified	November 24, 2020		evbox	troniq50	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.0.2r4a	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	No	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EVBox	Troniq Modular/Troniq High Power	Certified	May 26, 2023		evbox	troniq_modular_troniq_high_power	Direct connection	0	OCPP JSON 1.6	SIM, LAN	37715	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	Yes	No	No	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EVChargeking	ETap Pro Series	Certified	October 23, 2023		evchargeking	etap_pro_series	Proxy Connection	0	OCPP JSON 1.6	LAN	0.0.56	Not Tested	AC	T2 Socket	No	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVONITY	HD and PRO Series AC	Certified	October 23, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM	1.4.1	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
EVONITY	CF2-320 CF2C CFY CFM CFx	Certified	May 17, 2023		evonity	cf_series	Direct connection	0	OCPP JSON 1.6	SIM	V2.8.1	Not Tested	DC	CCS2 Cable	Optional	No	No	Unknown	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
EVTEC	10624.2A	Certified	Unknown		evtec	fast_charger	Unknown	0	OCPP JSON 1.6	Unknown	Unknown	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	Yes	Not tested	Unknown	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Fimer	Electra DC	Certified	August 1, 2022		fimer	electra_dc	Direct connection	0	OCPP JSON 1.6	SIM	MC_QCK_3.2_2CCS	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Unknown	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Fimer	Flexa AC	Certified	December 15, 2022		fimer	flexa_ac	Direct connection	0	OCPP JSON 1.6	SIM, LAN	02.17-01.23.00000.0822	Yes	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Flexicharge	Charge post /wallbox home charger	Certified	December 19, 2024	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.33.1-20092	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Floox	Lyra60	Certified	July 21, 2025		floox	lyra60_lite_lynx	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	LYRA_60v1.0.20	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Yes	The charger is to be used with only public simcards and public internet.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
FOX-ESS	A022KS1-E5-R2	Certified	November 4, 2024	FoxEss	foxess	22kw	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	2.05,1.25	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
FOX-ESS	C044KS2	Approved (Limited)	September 3, 2025	FoxEss	foxess	44kws2_limited	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	0.05,0.03,0.40,0.03	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested	Charger diagonistics are only supported with HTTP	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Free2move	eProWallbox	Approved (Limited)	April 26, 2024		free2move	eprowb_limited	Direct connection	0	OCPP JSON 1.6	SIM, WIFI	2.9.3	No	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested	GetDiagnostics missing	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
G2Mobility(Total_Energies)	Diva2/Alto/Soprano	Approved (Limited)	November 5, 2023		g2mobility	diva2_alto_soprano_limited	Direct connection	0	OCPP JSON 1.6	SIM	1.7.0c-quectel2.f1.6.2	No	AC	T2 Socket	No	No	No	No	Not tested	Not tested	Not tested	Lots of ws disconnections	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Garo	EntityPro	Certified	August 4, 2025		garo	pro	Proxy Connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	3.2.4	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Garo	LS4	Certified	August 1, 2019		garo_ab	ls4	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.10-7027(debug)	Not Tested	AC	T2 Socket	Unknown	No	No	Unknown	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Gewiss	Joinon(I-CON)	Certified	March 3, 2023		gewiss	joinon	Direct connection	0	OCPP JSON 1.6	SIM	2022.10.28.V_1_6_13	No	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
GL Charge	PublicBox/GlowBox Platinum	Certified	December 11, 2024	GL EVCCM	gl_charge	publicbox_glowbox_platinum	Direct connection	0	OCPP JSON 1.6	SIM, LAN	0.22/8,1.8,2.8	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Go-E	V3, V4, V5 Gemini Gemini 2.0	Approved (Limited)	October 2, 2024		go_e	v3_v4_v5_limited	Proxy Connection	0	OCPP JSON 1.6	SIM, WIFI	56.9	Yes	AC	T2 Socket	No	No	Yes	Yes	Yes	Yes	Not tested	GetDiagnostics not working	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Goneo	D2E-A10B-A Smart charging T2 Cable	Approved (Limited)	August 14, 2024		goneo	ic_cpd_limited	Direct connection	0	OCPP JSON 1.6	SIM	D2E-A10B-A	Yes	AC	T2 Cable	No	No	No	No	Not tested	Not tested	Not tested	Stop transaction is not always sent immediately after the charger is offline.	The charger also contains an e-sim which must be connected using the public address with Apn name "bics"
Green Wallbox	2 PRO MAX	Certified	August 23, 2024		green_wallbox	2pro_max	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.2.0	Yes	AC	T2 Socket	Optional	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Gresgying	F1-EU, F2-EU, F3-EU	Certified	April 27, 2023		gresgying	f1_f2_f3	Direct connection	0	OCPP JSON 1.6	SIM	2.4.0	No	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Gresgying	Turbo wallbox	Certified	April 18, 2024		gresgying	turbo_wallbox	Direct connection	0	OCPP JSON 1.6	LAN	C-V1.01.17 P-V1.01.14	No	AC	T2 Socket	No	No	No	Yes	Not tested	Not tested	Not tested	GetDiagnostics missing	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	Witty One	Certified	September 22, 2025		hager	witty_one	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	V1.1.5.2	Yes	AC	T2 Socket	Optional	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	Witty Park 2	Certified	December 5, 2025		hager	witty_park2	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.1.12.4	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	Witty Pro	Certified	September 22, 2025		hager	witty_pro	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	V1.1.5.2	Yes	AC	T2 Socket	Optional	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	XEV1R22T2 SocketTE (Witty Share)	Certified	March 28, 2022		hager	witty_share	Direct connection	0	OCPP JSON 1.6	LAN	v21.10.25-Zr-RC16	Not Tested	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	XEV6xxC (Witty Park)	Certified	March 24, 2023		hager	witty_park	Direct connection	0	OCPP JSON 1.6	LAN	0.99.0.10 / 9.0.0.7	Yes	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hager	XVL122S or C (Witty Plus)	Certified	May 12, 2025		hager	witty_plus	Direct connection	0	OCPP JSON 1.6	LAN	V1.1.1.2	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Heliox	Rapid 150	Certified	November 8, 2024		heliox	rapid_150	Proxy Connection	0	OCPP JSON 1.6	SIM	3.8.3	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Yes	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Heliox	Rapid 360	Certified	November 8, 2024		heliox	rapid_360	Proxy Connection	0	OCPP JSON 1.6	SIM	3.8.3	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Yes	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Heliox	Rapid 50	Approved (Limited)	February 2, 2024		heliox	rapid_50_limited	Direct connection	0	OCPP JSON 1.6	SIM	1.3.14	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	Communication with PRE SIM card. PRE has it s own connection for remote diagnostics, configuration and remote updates. Issues StopTransaction missing - power loss test	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Hellonext	H260	Certified	March 18, 2024		hellonext	h260	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.08.08.0601	Yes	DC	CCS2 Cable	Yes	No	No	Yes	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Hesotec	eSat r10, r20 eBox wr30-r, wr30-l	Certified	November 15, 2024		hesotec	esat_r10_r20_ebox_wr30r_wr30l	Direct connection	0	OCPP JSON 1.6	LAN	c24.004p23.019h24.003s24.003d24.003	Not Tested	AC	T2 Socket	Yes	Yes	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Hesotec	Sr10, r10, r20, wr30	Certified	February 28, 2023		hesotec	sr10_r10_r20_wr30	Direct connection	0	OCPP JSON 1.6	LAN	1,402	Not Tested	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
HJLCHARGER (HG POWER)	ENC-DCL120(B Series)	Certified	July 2, 2025		hjlcharger	enc_dcl120_b_series	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	1.0.16.0611	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Huawei	DS720	Certified	December 12, 2025		huawei	ds720	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	V100R024C10SPC150	Not Tested	DC	T2 Socket	Yes	Not tested	Yes	Unknown	Not tested	Not tested	Not tested	Diagnostics of the charger can always be asked from the vendor directly.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
i-charging	blueberry	Certified	April 5, 2023		i_charging	blueberry	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.4.0.	Yes	DC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
IES Synergy	WallboxG3, KeyWatt50 Station 24k/50k/100k	Certified	December 9, 2023		ies	key_watt_g3	Direct connection	0	OCPP JSON 1.6	SIM	22PRO017362_V021.822	Yes	DC	CCS2 Cable	Yes	No	Yes	Unknown	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Iglu Tech	C320002100	Certified	February 1, 2024		iglu_tech	c320002100	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.0.4/1.0.5/0.17	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	Iglu also uses StuartEnergy	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Inbalance Grid	PC1/PC1c Series	Certified	April 29, 2024		inbalance_grid	pc1_pc1c_series	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.3.1	Yes	AC	T2 Socket	Optional	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Infypower	EXP400	Approved (Limited)	April 8, 2026		Infypower	exp400	Direct connection	0	OCPP JSON 1.6	SIM, LAN	N5.5.12T14,1.93,--&--,220	No	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	GetDiagnostics upload failed	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Ingeteam	RAPID 50/60	Certified	March 15, 2022		ingeteam	rapid50_60	Direct connection	0	OCPP JSON 1.6	SIM	2024.06.19	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Ingeteam	Ingerev Fusion Eichrecht	Certified	September 22, 2022		ingeteam	ingerev_fusion_e	Direct connection	0	OCPP JSON 1.6	SIM	2022.09.01	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ingeteam	Ingerev Fusion M3T32A	Certified	March 14, 2022		ingeteam	ingerev_fusion	Direct connection	0	OCPP JSON 1.6	LAN	2021.12.16	Not Tested	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
INNC	NextGen DC 180/300kW	Certified	December 2, 2025	Vector vSECC	innc	nextgen	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.9.0	Yes	DC	T2 Cable	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
IoCharger	IOCxxxxxx, IOCAHxx IOCAPxx, IOCAWxx	Certified	October 21, 2024		iocharger	ioc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	24083001-24083001-24032001	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ISKRAEMECO	AIO180, WB30, WB40	Certified	October 15, 2024		iskraemeco	aio180_wb30_wb40	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.2.1	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Kathrein	AC40, AC60	Certified	July 7, 2023		kathrein	ac40_60	Direct connection	0	OCPP JSON 1.6	LAN	1.0.5-3-g6339137-dirty	No	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Keba AG	P40 (C6S3ALP0-LS1R1111BL0)	Certified	February 17, 2026		keba	p40	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	1.4.2	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Keba AG	KC-P30-ES2400H2-L0R	Certified	May 26, 2021		keba	p30	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.12.0	Not Tested	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Kempower	DCS, ACS, CU, PU, SC MV, S, C and T Series	Certified	December 8, 2025		kempower	ac_dc	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	1.1.6 and 3.4.8	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Unknown	Not tested	Not tested	Not tested	Firmware updates must be performed via the manufacturer.	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Kreisel	Chimero DC180	Certified	January 24, 2024		kreisel	chimero	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.0.0	No	DC	CCS2 Cable	Yes	No	No	Yes	Not tested	Not tested	Yes		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Kuon(kuon.nl)	dc80	Certified	June 10, 2026		kuon	dc30_dc200	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	TCU0045EVB01_V1.5.2	Not supported	DC	T2 Cable	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
LafonTechnologies/Madic	Pulse 20/40/80 DC	Certified	September 29, 2026		lafon	pulse20_80_dc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.3.8.7	Not supported	DC	CCS2 Cable	Yes	No	Not tested	Not tested	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
LafonTechnologies/Madic	Pulse 50/60 DC	Certified	January 1, 2024		lafon	pulse50_60_dc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.10.306	No	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
LafonTechnologies/Madic	Pluse WB/GL/WL AC	Certified	March 28, 2023		lafon	pulse_wb_gl_wl	Direct connection	0	OCPP JSON 1.6	SIM	3.11.123.WA	No	AC	T2 Socket	Yes	No	Yes	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
LCTC Linkcharging	Ejornee S-Series (Commercial/Public)	Certified	July 26, 2024		lctc	s_series	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	83105120341_ASUBWGKE4BU1_V101B01D34	No	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Legrand	Green'up Premium	Certified	April 4, 2024		legrand	green_up	Direct connection	0	OCPP JSON 1.6	LAN	V01.17.00	Not Tested	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Lenergizee	Wallbox AC 22 kW	Certified	April 25, 2024	Phoenix-charx	lenergizee	wallbox_ac	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.5.0	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Loxone	Wallbox 11kW	Approved (Limited)	October 24, 2025		loxone	wallbox_limited	Direct connection	0	OCPP JSON 1.6	LAN	1.4.0	No	AC	T2 Socket	Yes	No	Not tested	Not tested	Not tested	Not tested	Not tested	Power loss and Soft reset with transaction problems. Stop with EV.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Lumosa B.V	Track	Certified	April 13, 2026		lumosa	track	Direct connection	0	OCPP JSON 1.6	SIM, LAN	7.10.0	No	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
MagnumCap	MC QCA150H	Certified	February 9, 2022		magnum_cap	mc_qca150h	Direct connection	0	OCPP JSON 1.6	SIM, LAN	MC_QCK_1.2-11	Not Tested	DC	CCS2 Cable	Yes	No	No	Unknown	Not tested	Not tested	Not tested	Eichrecht, SmartChargin in development	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Mennekes	Charging column Smart Premium / Smart T	Certified	September 6, 2022	ACU	mennekes	acu_series	Direct connection	0	OCPP JSON 1.6	LAN	5.12.6-11302	Yes	AC	T2 Socket	Yes	Yes	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Ladesäule Premium 22 Ueberspg, Wandladestation Premium 22	Certified	September 6, 2022	ACU	mennekes	acu_series	Direct connection	0	OCPP JSON 1.6	LAN	5.12.6-11302	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Amtron Professional (137xxx,136xxx) CC612_2M4PR, 2S0PR 2M4R, 2S0R	Certified	August 23, 2022	CC612	mennekes	amtron_pro	Direct connection	0	OCPP JSON 1.6	SIM	5.12.4-11256	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Amtron Professional Eichrecht (138xxx) CC612_2M4PR, 2S0PR, 2M4R, 2S0R	Certified	June 25, 2020	CC612	mennekes	amtron_pro_eichrecht	Direct connection	0	OCPP JSON 1.6	SIM	4.61-5996	Yes	AC	T2 Socket	Unknown	Yes	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Amtron Professional TwinCharge CC612_2M4PR_TC, 2S0PR_TC 2M4R_TC, 2S0R_TC	Certified	June 25, 2020	CC612	mennekes	amtron_pro_twincharge	Direct connection	0	OCPP JSON 1.6	SIM	4.61-5996	Yes	AC	T2 Socket	Unknown	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Smart T PNC CC612_2M4PR_ST, 2S0PR_ST, 2M4R_ST, 2S0R_ST	Certified	August 23, 2022	CC612	mennekes	smart_t_pnc	Direct connection	0	OCPP JSON 1.6	SIM	5.22.3-13380	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	Amedio Professional CC612_2M4PR_X2 2S0PR_X2, 2M4R_X2, 2S0R_X2	Certified	September 6, 2022	ICC1622	mennekes	amedio_pro	Direct connection	0	OCPP JSON 1.6	LAN	5.12.6-11302	Yes	AC	T2 Socket	Yes	Yes	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Mennekes	4Business710-780	Certified	August 23, 2022		mennekes	4business710_780	Direct connection	0	OCPP JSON 1.6	LAN		Not Tested	DC	T2 Cable	Yes	Yes	Yes	Yes	Not tested	Not tested	Not tested	Business currently has 3 variants: 730 (4Gm MID meter, no Eichrecht), 760 (no 4G, Eichrecht) and 780 (4G and Eichrecht)	
Nodal	Session 40S/40D	Certified	October 23, 2026		nodal	session_40_s_d	Direct connection	0 + 2	OCPP JSON 1.6	SIM, LAN	DC_V30.69_0731;UULN;DW_T5_L10;1.1.27.4	yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Yes	Yes	Not tested		
Morek	DC MEV 20/120/180	Certified	January 23, 2025		morek	dc30_120_180	Direct connection	0	OCPP JSON 1.6	SIM, LAN	CSCU_C2032_MEV2.7.0	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Morek	AC MEV07DREWNNT2 Socket	Certified	January 23, 2025		morek	ac22kw	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	A0-MEV-V2.1.1-W1.4.1	No	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
NCT	CC Light	Certified	March 20, 2024	Bender	nct	cc_light_bender	Direct connection	0	OCPP JSON 1.6	SIM, LAN	5.29.2	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ND Charge	ADC	Certified	October 15, 2024		nd_charge	adc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	ORPi v 1.06_4_pl	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	No	No	No	No	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
NewInergyGmbh	DaheimLaderBusinessPro	Certified	April 13, 2026		new_inergy_gmbh	daheim_lader_businesspro	Direct connection	2	OCPP JSON 1.6	SIM, WIFI,LAN	1.0.18	yes	AC	T2 Socket	yes	Yes	yes	yes	Not tested	Not tested	Not tested	The Businesspro verson supports Echirecht	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
NewInergyGmbh	DaheimLaderTouchPro	Certified	April 13, 2026		new_inergy_gmbh	daheim_lader_touchpro	Direct connection	2	OCPP JSON 1.6	SIM, WIFI,LAN	1.0.18	Yes	AC	T2 Cable	Yes	No	yes	yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Nexans	Agicity (Enovate Pro22/44)	Certified	Unknown		enovates	pro22_pro44	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Unknown	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
NexBlue	Edge 2 and Max, Delta (Max)	Certified	April 17, 2026		nexblue	edge_delta_max	Direct connection	2	OCPP JSON 1.6	SIM, LAN	03.08.08	No	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested	The manufacturer is responsible for diagnostics and firmware updates.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Nidec Conversion	DPDT-360-360	Certified	June 5, 2025		nidec	dpdt_360	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	v03.00.003_rc06	Yes	DC	T2 Cable	Yes	Yes	Yes	Yes	Not tested	Not tested	Not tested	Charger does not have an emergency button.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Nidec Conversion	DC 120/360	Certified	January 10, 2024		nidec	dc_120	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V02.00.289	No	DC	CCS2 Cable	Optional	No	No	No	Not tested	Not tested	Not tested	Eichrecht, SmartChargin in development	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Ohme Operations UK Ltd	ePOD 22KW 4G, ePOD S 22kW 4G	Certified	September 18, 2025		ohme	epod	Proxy Connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	V1.08_202510041	No	AC	T2 Socket	No	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ohme Operations UK Ltd	Home Go V1.0 (Smart Charging Cable)	Approved (Limited)	August 25, 2023		ohme	home_go_v1.0_limited	Proxy Connection	0	OCPP JSON 1.6	SIM	V1.32_202307131	Not Tested	AC	T2 Socket	No	No	No	No	Not tested	Not tested	Not tested	Stop transaction is not always sent immediately after the charger is offline.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ohme Operations UK Ltd	Home Pro 11KW 4G non MID, Home Pro 11KW 4G non MID Delta	Certified	May 23, 2025		ohme	home_pro	Proxy Connection	0	OCPP JSON 1.6	Public SIM	V1.20_202505231/ Delta: v2.1_202510111	Not Tested	AC	T2 Socket	No	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Orbis	Viaris UNI	Certified	July 4, 2024		orbis	viaris_uni	Direct connection	0	OCPP JSON 1.6	LAN	7.2.59.101	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
OWA6	Quadruple, douple, single	Certified	March 24, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	LAN	V1.3.1	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Pacesetter New Energy Co., Ltd. (PNE)	SDTE180-1000-U2000	Certified	March 2, 2026		pacesetter_new_energy	sdte180	Direct connection	0	OCPP JSON 1.6	LAN	V 1.30.01.55	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Phoenix Contact	DC NW 180	Certified	April 25, 2024	Phoenix DC	phoenix_contact	dc_nw_180	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.05	No	DC	CCS2 Cable	Yes	No	No	Yes	Not tested	Not tested	Not tested	Dedicated service connection provided by manufacturer for diagnostics and updates	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Phoenix Contact	Charge Repay Service	Approved (Limited)	January 10, 2025		phoenix_contact	repay_service_limited	Direct connection	0	OCPP JSON 1.6	SIM, LAN	No data availible	No	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested	This is not a charger, but a repay service.	The Tag ID must be registered in EVC-NET before transactions can be sent to the Backoffice. Otherwise the transactions are not billable.
Pluon	ACP Series	Certified	January 27, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM	V1.2.0	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Pluon	DCP Series Slim,Regular,High	Certified	February 19, 2024		pluon	dcp_series	Direct connection	0	OCPP JSON 1.6	SIM	V5.0.2	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Power Electronics	NB120/NB240	Approved (Limited)	November 9, 2023		power_electronics	nb120_nb240_limited	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.1.1-2	No	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested	Not tested	GetDiagnostics missing	https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Pre Biel	PRE_BIEL Poland	Certified	March 7, 2019		pre_biel	pre_biel	Direct connection	0	OCPP JSON 1.6	SIM	0.9.12rc1	Not Tested	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ProdriveTechnologies	Dual	Certified	October 20, 2026		prodrive	peblar_dual	Direct connection	2	OCPP JSON 1.6	SIM	1.10.0	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ProdriveTechnologies	Peblar Home(+)/Business	Certified	July 13, 2026		prodrive	peblar_home_business	Direct connection	2	OCPP JSON 1.6	SIM	1.4.0+1+PT-1 1.9.1	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Quintiens NV	Q1/Q2	Certified	May 31, 2024	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM	1.5.2release+3322.20240319.b619a042f	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Raedian	GEMINI_A&B	Approved (Limited)	June 20, 2025		raedian	gemini_a_b_limited	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	s8104000012111_2.1.3	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	Diagnostics with ftp not supported rather supports http.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Raedian	NEO & NEX_22S_A	Approved (Limited)	March 20, 2025		raedian	neo_nex_limited	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	s8100000001231_2.0.6_133	Not Tested	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested	Diagnostics with ftp not supported rather supports http.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ratio	io7	Certified	July 1, 2024	versinetic	ratio	io7	Direct connection	0	OCPP JSON 1.6	LAN	1.4.8	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Ratio	Smart/Solar/IO5/IO6	Approved (Limited)	July 9, 2024		ratio	smart_limited	Direct connection	0	OCPP JSON 1.6	LAN	3.9.0_RC3	Not Tested	AC	T2 Socket	No	No	Yes	No	Not tested	Not tested	Not tested	GetDiagnostics is missing	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Reno Energy	Volt'R	Certified	January 31, 2025	Prodrive	reno_energy	volt_r	Direct connection	2	OCPP JSON 1.6	SIM	1.5.0+1+WL-1	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Scame Parre S.p.A	SBC-0	Certified	January 6, 2022		scame	sbc_0	Direct connection	0	OCPP JSON 1.6	LAN	1.3.11	Not Tested	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
SCAPO GmbH and BEGA Gantenbrink-Leuchten KG	Comfort/Vision/Bega	Certified	June 14, 2024	Wallbe controller	wallbe	smart_charge_control	Direct connection	0	OCPP JSON 1.6	Public SIM	BE-03.02.13	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	Parkplatz P3(Wallbe Controller)	Certified	February 3, 2023	Wallbe controller	wallbe	smart_charge_control	Direct connection	0	OCPP JSON 1.6	SIM	BE-03.01.33	Not Tested	AC	T2 Socket	Yes	Yes	Yes	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	Evlink Pro DC 120/150/180	Certified	April 25, 2024		schneider	evlink_pro_dc_100_series	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.3.16	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Schneider Electric	Evlink Parking	Certified	May 2, 2019		schneider	evlink_smart	Direct connection	0	OCPP JSON 1.6	SIM	3.3.0.7	Not Tested	AC	T2 Socket	Yes	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	Evlink Pro AC (Eichrecht)	Certified	April 11, 2023		schneider	evlink_pro_ac_e	Direct connection	0	OCPP JSON 1.6	LAN	1.2.1	Yes	AC	T2 Socket	Yes	Yes	Yes	Unknown	Not tested	Not tested	Not tested	MeterValuesStartFromZero must beunchecked. Eichrecht verification only works with manual entry.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	Evlink Pro AC	Certified	August 11, 2022		schneider	evlink_pro_ac	Direct connection	0	OCPP JSON 1.6	SIM	1.0.1	Not Tested	AC	T2 Socket	Unknown	No	No	Unknown	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	Evlink Pro DC 60	Certified	June 21, 2024		schneider	evlink_pro_ac_60	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.4.04	Yes	DC	T2 Socket	Optional	No	Yes	Yes	Not tested	Not tested	Not tested		https://support.lastmilesolutions.com/92b3z2a5bc7de1f0g1h4ij5k5l6m5n8o7p/setup-guides/register-charge-points-in-evc-net/#step-2-update-charge-point-settings
Schneider Electric	Evlink Smart Wallbox	Certified	May 2, 2019		schneider	evlink_smart	Direct connection	0	OCPP JSON 1.6	SIM	1.3.6	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Schneider Electric	SE Charge Pro	Certified	May 20, 2025		schneider	charge_pro	Direct connection	0	OCPP JSON 1.6	SIM	1.21.1	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Seijsener	ALPX/SEVbox	Certified	May 30, 2023	Phoenix-charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Yes	AC	T2 Socket	Unknown	No	No	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
SETEC Power Co.,Ltd	CPM SETEC DC/AC	Certified	July 14, 2019		setec	cpm_dc_ac	Direct connection	0	OCPP SOAP 1.5	SIM	1.0	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Alfen	Lolo 3	Approved (Limited)	October 24, 2024		shell_newmotion	lolo3_limited	Direct connection	0	OCPP JSON 1.6	LAN	4.7.1-3158	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	*ConnectionTimeOut test (RFid only) is not working!*	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Lite 2.x	Certified	September 24, 2024	eRTU3	shell_newmotion	business_lite_2.x	Direct connection	0	OCPP JSON 1.6	LAN	1.13.1.3@118.1.1	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Lite View	Approved (Limited)	October 24, 2024	eRTU3	shell_newmotion	business_lite_view_limited	Direct connection	0	OCPP JSON 1.6	LAN	1.10.2.1@104.31.10 3_256d3	Not Tested	AC	T2 Socket	Yes	No	Yes	No	Not tested	Not tested	Not tested	GetDiagnostics:Not supported.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Pro 2.x	Certified	September 23, 2024	eRTU3	shell_newmotion	business_pro_2.x	Direct connection	0	OCPP JSON 1.6	LAN	1.7.9.1.4@103.17.11 3_256d3 1.13.1.3@118.1.1	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Pro View	Certified	October 24, 2024	eRTU3	shell_newmotion	business_pro_view	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.10.0@104.30.3 3_256d3	Not Tested	AC	T2 Socket	Yes	No	Yes	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Home Advanced 2.x	Certified	September 24, 2024	eRTU3	shell_newmotion	home_advanced_2.x	Direct connection	0	OCPP JSON 1.6	LAN	1.13.1.3@118.1.1	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Home Advanced View	Certified	July 28, 2025	eRTU3	shell_newmotion	home_advanced_view	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.10.0@104.30.3 3_256d3	Not Tested	AC	T2 Socket	Yes	No	Yes	No	Yes	Yes	Not tested	Charger profiles work with start schedules.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Lite 3.0	Certified	March 14, 2025	eRTU6	shell_newmotion	business_lite_3.0	Direct connection	0+2	OCPP JSON 1.6	LAN	1.13.0.1@ 2.4.6	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested	Master slave configured	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Business Pro 3.0	Certified	March 13, 2025	eRTU6	shell_newmotion	business_pro_3.0	Direct connection	0+2	OCPP JSON 1.6	SIM	1.13.0.1@2.4.6	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Enovates	Home Advanced 3.0	Certified	March 13, 2025	eRTU6	shell_newmotion	home_advanced_3.0	Direct connection	0+2	OCPP JSON 1.6	SIM	1.13.0.1@2.4.6	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Liteon	Lolo x/pro/4	Approved (Limited)	May 15, 2025		shell_newmotion	lolox_limited	Direct connection	0	OCPP JSON 1.5	LAN	V1.18.00 (CB: V1.08)	Yes	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested	At powerloss the transcations are not closed.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shell Recharge/NewMotion-Prodrive	Advanced Flex 1.x	Certified	September 3, 2025		shell_newmotion	advanced_flex_1.x	Direct connection	2	OCPP JSON 1.6	SIM	*1.8.0+1+SHELL-1*	Yes	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Shenzhen ELECQ Technology Co	AE105	Certified	June 2, 2025		elecq	ae105	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	1_V1.0.30	Through APP	AC	T2 Socket	Optional	No	Yes	Yes	Not tested	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Sichuan Jemmeo Technology Co. Ltd.	GS7-AC-B01	Certified	June 13, 2024		sichuan_jemmeo	gs7_ac_b01	Direct connection	0	OCPP JSON 1.6	LAN	GS22_AC_3PV110	Not Tested	AC	T2 Socket	No	No	Yes	Yes	Not tested	Not tested	Not tested	Configuration keys are only set 1 by 1 via backoffice.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.

Siemens AG	SICHARGE D	Certified	June 20, 2022		siemens	sicharge_d	Direct connection	0	OCPP JSON 1.6	SIM	V2.5.2-0-G244C9F5	No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Yes	Yes	Not tested	Yes		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Siemens AG	Unity90	Approved (Limited)	October 5, 2023		siemens	unity90_limited	Direct connection	0	OCPP JSON 1.6	SIM, LAN	0.8.4	No	DC	CCS2 Cable	Yes	No	No	No	No	Not tested	Not tested	GetDiagnostics missing	https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Siemens AG	SICHARGE CC AC22	Approved (Limited)	March 19, 2024		siemens	sicharge_cc_ac22_limited	Direct connection	0	OCPP JSON 1.6	LAN	11-v31ocpp16-74	No	AC	T2 Socket	Yes	No	No	Yes	Yes	Not tested	Not tested	Charger does not come online after power interruption.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Siemens AG	Versicharge	Approved (Limited)	July 27, 2023		siemens	versicharge_limited	Direct connection	0	OCPP JSON 1.6	SIM	2.126.17 No	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Yes	Yes	Not tested	Not tested	GetDiagnostics and RemoteUpdate are not supported through OCPP, available only directly from Siemens cloud only with public SIM card. LMS APN SIM CARDS CANNOT BE USED. CPO shall provide public SIM cards for connection	https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Sinexcel	SEC 30/80/160/240/480	Certified	August 19, 2025		sinexcel	sec_dc	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.6_OCPP_105.02	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Sinexcel	CEEUAC 22kw	Certified	February 24, 2025		sinexcel	ceeuac	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	OCPP1.6_V000.061.062	Not Tested	AC	T2 Socket	Yes	No	No	No	No	Not tested	Not tested	Simcard ICCID and IMSI is not mentioned in the boot notification.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
SMA Technologies	EV Charger Business	Certified	October 13, 2023	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	LAN	5.29.1-13419	Not Tested	AC	T2 Cable	Yes	No	Yes	Yes	Not tested	Not tested	Walther-Werke White label charger	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Smappee	EVWB-332-C2R-E-W, EVWB-132-CXR-E-W	Certified	May 26, 2021		smappee	evwb_x32_cxr	Proxy Connection	0	OCPP JSON 1.6	LAN	EC 2.26	Not Tested	AC	T2 Socket	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
SOLA EV	SPEED-E	Certified	August 17, 2022		sola	speed_e	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.07.25Y	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
SOLA EV	STAND-E	Certified	December 6, 2021		sola	stand_e	Direct connection	0	OCPP JSON 1.6	SIM	1.01SY	Not Tested	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
SOLA EV	WALL-E	Certified	March 31, 2023		sola	wall_e	Direct connection	0	OCPP JSON 1.6	SIM	1--00-0	Not Tested	AC	T2 Socket	Optional	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Solax power	FDC_120_180_240_300_360k	Certified	June 15, 2026		solax_power	fdc_series	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	26.0610	Not Tested	DC	T2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Sparklin	Spark1(No RFID, only remote)	Certified	February 17, 2023		sparklin	spark1	Direct connection	0	OCPP JSON 1.6	Public SIM	0.0.1	No	AC	schuko	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Spelsberg	SmartPro	Certified	October 7, 2024	Bender	bender	CC613	Direct connection	0	OCPP JSON 1.6	LAN	5.33.0-19869	Not Tested	AC	T2 Socket	Optional	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Athena 60_DH-DC060DH0S8-I	Certified	September 20, 2023		starcharge	athena_60	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.3007.3	Yes	DC	CCS2 Cable	Yes	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Jupiter 60_DC060DEN0S2-A	Certified	July 13, 2022		starcharge	jupiter	Direct connection	0	OCPP JSON 1.6	SIM	1.5.1.6.9S20B	Yes	DC	CCS2 Cable	Yes	No	Yes	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Star Charge	Neptune_DC1000SC3I000Z-S30	Certified	July 18, 2023		starcharge	neptune	Direct connection	0	OCPP JSON 1.6	SIM	1.3.0.0.1bi.1	Not Tested	DC	CCS2 Cable	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Titan V3_DH-DC180DS2I6-D	Certified	April 27, 2023		starcharge	dh_dc180ds2i6	Direct connection	0	OCPP JSON 1.6	SIM	1.3.0.0.2bi102	Yes	DC	CCS2 Cable	Yes	No	No	Yes	Yes	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Star Charge	Titan_DH-DC180DS0S8	Certified	July 22, 2022		starcharge	titan	Direct connection	0	OCPP JSON 1.6	SIM	1.3.0.1.1bi155	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Star Charge	Venus 30_DH-DC030DH0S17	Certified	August 12, 2022		starcharge	venus	Direct connection	0	OCPP JSON 1.6	SIM	1.2.0.1.9-0118	Yes	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Star Charge	Artemis_AC0110EN02S05	Certified	October 17, 2023		starcharge	artemis_ac	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.0.0bi1.0.0_Artemis_TIC	No	AC	T2 Socket	Yes	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Aurora MID_DH-AC0110XG70	Certified	June 16, 2022		starcharge	aurora	Direct connection	0	OCPP JSON 1.6	SIM	1.0.0.0.6b106_MID11	Not Tested	AC	T2 Socket	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Saturn 22KW (Cyber Security Version) AC0220NCM4L	Certified	April 29, 2024		starcharge	saturn22kw	Direct connection	0	OCPP JSON 1.6	SIM	20.173.06126	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Saturn 22KW_DH-AC0220XG58	Certified	February 19, 2024		starcharge	dh_ac0220xg	Direct connection	0	OCPP JSON 1.6	SIM	1.5.1.3.1bi108 and 1.5.1.6.1	Not Tested	AC	T2 Socket	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Star Charge	Telesto_AC0220XG58	Certified	October 20, 2023		starcharge	telesto	Direct connection	0	OCPP JSON 1.6	SIM	1.0.0.1.7	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Stegen Electronics	SmartEVSE controller	Certified	June 20, 2025	SmartEVSE	stegen_electronics	smartevse	Direct connection	0	OCPP JSON 1.6	Wifi	V3.7.4	Not Tested	AC	T2 Socket	Yes	No	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Stroohm	Zencharger	Certified	August 14, 2023	Prodrive	stroohm	zencharger	Direct connection	2	OCPP JSON 1.6	SIM	1.1.1+1+CHARGEPOINT-2	No	AC	T2 Socket	Yes	Not tested	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Sungrow Power Supply Co	CDC1000E	Approved (Limited)	October 12, 2024		sungrow	cdc1000e_limited	Direct connection	0 + 2	OCPP JSON 1.6	VPN SIM	DE.303.FFF.20.14	Not Tested	DC	CCS2 Cable	yes	Not tested	yes	Not tested	Not tested	Not tested	SIM-ICCID not mentioned in BootNotification.	https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Sungrow Power Supply Co	iDC330E	Certified	February 20, 2023		sungrow	idc330e	Direct connection	0	OCPP JSON 1.6	SIM	1.0.8	Not Tested	DC	CCS2 Cable	Yes	No	Unknown	Not tested	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Sungrow Power Supply Co	iDC180E	Certified	January 10, 2023		sungrow	idc180e	Direct connection	0	OCPP JSON 1.6	SIM, LAN	2.4.0	No	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Sungrow Power Supply Co	iDC480E	Certified	December 10, 2024		sungrow	idc480e	Direct connection	0	OCPP JSON 1.6	SIM, LAN	09.001.001.000.006	Not Tested	DC	CCS2 Cable	Yes	No	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Sungrow Power Supply Co	AC22E-G2	Certified	August 5, 2024		sungrow	ac22e	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	Yes	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	The charger doesnot support LMS simcards.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Surpass Sun Energy	ZEVOC-150	Certified	July 31, 2026		surpass_sun_energy	zevoc_150	Direct connection	2	OCPP JSON 1.6	LAN/WIFI	V5_16_3_99	Yes	DC	CCS2 Cable	Yes	No	Yes	No	Not tested	Not tested	limit of 0kw is not supported.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Technogan GmbH	TEFLW Series TEP4 or & TEP4(HAK), TEW3 or 4	Certified	December 12, 2025		technogan	twp_w_series	Direct connection	1	OCPP JSON 1.6	SIM, LAN	Isp-ou_0.2.0-20251202184908 Yes	AC	T2 Socket	Yes	Yes	Yes	Yes	Yes	Not tested	Not tested	Echrecht verification works only with transparencsoftware-1.2.0!	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Technogan GmbH	TEP4 HAK, PBD(TEP8) HAKTITHAKPI	Certified	December 5, 2022		technogan	p_series	Direct connection	0	OCPP JSON 1.6	SIM	11-v51ocpp16-75.421,0.8.7-git+1666869543+4%2009	Not Tested	AC	T2 Socket	Optional	Yes	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Technocity	UrbanElec (range)	Certified	October 16, 2023		technocity	urbanelec	Direct connection	0	OCPP JSON 1.6	LAN	3.9.7	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Teltonika Energy	TeltoCharge	Certified	July 21, 2026		teltonika_energy	teltocharge	Direct connection	0	OCPP JSON 1.6	LAN	V1.10.9 v1.16.4	Yes	AC	T2 Socket	No	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Tesla	WC3 Wall Connector MID	Approved (Limited)	September 4, 2025		tesla	wc3_limited	Direct connection	2	OCPP JSON 1.6	Wifi	25.26.1	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Not tested	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Tritium	RTM	Certified	December 27, 2022		tritium	rtm	Direct connection	0	OCPP JSON 1.6	SIM	csb.22.2.3.0_dev4	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Tritium	TRI93-50-01	Certified	Unknown		tritium	tri93_50_06	Direct connection	0	OCPP JSON 1.6	Unknown	Not Tested	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Tritium	Veefil	Certified	October 25, 2018		tritium	veefil	Direct connection	0	OCPP JSON 1.6	SIM	V2.1.4	Yes	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
V2C	PDU1PRO32-3	Certified	March 28, 2025		v2c	pdu1pro32_3	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.7.1	No	AC	T2 Socket	Yes	No	Not tested	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
V2C	Trydan and Trydan Pro	Certified	March 28, 2025		v2c	trydan	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	4.0.0	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	Sim ICCID not mentioned in boot notification But will be implemented in the next firmware release after 4.0.0	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Valeo	INEEZ Product Range	Certified	October 21, 2022		valeo	ineez	Direct connection	0	OCPP JSON 1.6	LAN	d2c71d1ac7091983b8f4a65c0624c98ac460adc62	Not Tested	AC	T2 Socket/Cable	Yes	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Van der Sijs	LaadpleinDC00x &/...(combinations)	Certified	March 10, 2026		van_der_sijs	laadplein	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V5.0.2	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Not tested	Yes	Not tested	Not tested	GetDiagnostics issue - Diagnostics and Firmware updates available via the manufacturer	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Vector	DutchCharger DC40	Certified	December 3, 2024	Vector vECC	vector	dutchcharge_dc40	Direct connection	0	OCPP JSON 1.6	SIM, LAN	3.3.1	Not Tested	DC	T2 Socket	Yes	No	No	No	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Vestel	EVD6 DC	Certified	December 9, 2025		vestel	evc_06	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	0.1.96.2_1.0.55.0_2.0.92.0_2.0.92.0_6.0.0	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	Yes	Unknown	Yes	Not tested	When the local list is sent to the charger, it disconnects the charger connection for about 2 minutes. Firmware update not tested.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Vestel	EVC10 (Gemini) AC Echrecht	Certified	August 25, 2026		vestel	evc_10	Direct connection	0 + 2	OCPP JSON 1.6	SIM, WIFI,LAN	v4.68.28-1.10.54.3-v8.1.28	Yes	AC	T2 Socket	Optional	Yes	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Vestel	EVC16 DC	Certified	December 16, 2025		vestel	evc_16	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	0.3.46.32_3.0.15.0_2.0.96.0_2.0.96.0_6.0.0	Not Tested	DC	CCS2 Cable	Yes	No	Yes	Unknown	Yes	Not tested	Local list does not work.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Vestel	EVD24 Echrecht	Certified	March 18, 2024		vestel	evc_04	Direct connection	0	OCPP JSON 1.6	SIM, LAN	v3.1.45.0-1.0.143.0-v7.0.11	Yes	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Vestel	EVD24	Certified	February 27, 2020		vestel	evc_04	Direct connection	0	OCPP JSON 1.6	SIM	V1.62.0-1.0.76.1	Yes	AC	T2 Socket	Unknown	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Veton	ONE_TWO	Certified	January 31, 2023	Phoenix charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	LAN	V1.3.3	Yes	AC	T2 Socket	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Volt Time	Smart Un	Certified	June 27, 2024	verschelte	volt_time	source	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.4.8	Yes	AC	T2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Voltowa	DMYE, DMYE, hrrvt, rrhvt, hrvvt	Certified	April 2, 2025		voltowa	dc_d_series	Direct connection	0	OCPP JSON 1.6	SIM	V4.11.M0	Not Tested	AC/DC	CCS2 Cable T2 Socket/Cable	Yes	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
VOOL	CC22K1X	Approved (Limited)	May 14, 2025		vool	cc22k1x_limited	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	V1.9.27	Not Tested	AC	T2 Socket	Yes	No	No	No	Not tested	Not tested	Diagnostics not supported, Reasons for commit at hard and soft rest are set at other.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wallbe	Smart Charge Control	Certified	August 13, 2019	Wallbe controller	wallbe	smart_charge_control	Direct connection	0	OCPP JSON 1.6	SIM	BM-01.01.19	No	AC	T2 Socket	Unknown	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wallbox	Commander 2 CMX2	Certified	March 2, 2023		wallbox	commander_2_cmx2	Direct connection	0	OCPP JSON 1.6	LAN	5.16.26	Not Tested	AC	T2 Cable	No	No	No	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wallbox	Supernova	Certified	February 20, 2023		wallbox	supernova	Direct connection	0	OCPP JSON 1.6	SIM, LAN	1.12.45	Not Tested	DC	CCS2 Cable	No	No	No	Unknown	Not tested	Not tested		https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings
Wallbox	Copper_Pulsar+	Certified	September 4, 2024		wallbox	copper_pulsar+	Direct connection	0	OCPP JSON 1.6	SIM, LAN	6.11.16	No	AC	T2 Socket	Optional	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wallbox	Copper SB	Certified	August 12, 2024		wallbox	copper_sb	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	6.6.8	Not Tested	AC	T2 Socket	Optional	No	Yes	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Walther-Werke	SmartEVO+	Certified	September 18, 2023	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM	5.21.2.13536	Not Tested	AC	T2 Socket	Optional	Yes	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
We Drive Solar	V1.1/wand-Bender	Certified	Unknown	Bender	bender	cc613	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	No	AC	T2 Socket	Unknown	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
We Drive Solar	V1.1/wand-Phoenix	Certified	Unknown	Phoenix charx	phoenix_contact	charx	Direct connection	0	OCPP JSON 1.6	SIM	Unknown	Yes	AC	T2 Socket	Unknown	No	No	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
We Drive Solar	Solar City V1.3	Certified	March 31, 2026	Super-8	we_drive_solar	solar_city_v13	Direct connection	0	OCPP JSON 1.6	SIM, LAN	ac_v1.9.0-RC2_ac_v0.23.4	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested	WebsocketPingInterval must be set to 30 seconds.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
We Drive Solar	Solar City V1.2	Certified	December 20, 2024	Super-8	we_drive_solar	solar_city_v12	Direct connection	0	OCPP JSON 1.6	SIM, LAN	ac_v1.0.0-rc4_ac_v0.14.1	No	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Webasto	Webasto_AC_Live	Certified	December 10, 2021		webasto	webasto_ac_live	Not tested	0	OCPP JSON 1.6	SIM	5.11.1-10129	Not Tested	AC	T2 Socket	Unknown	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wellborne	WB-22S-S	Certified	June 7, 2022		wellborne	wb_22_d	Direct connection	0	OCPP JSON 1.6	SIM	AC22K_1P_WL_V57_t02	Not Tested	AC	T2 Socket	No	No	No	Yes	Unknown	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Wolun New Energy (Sup-Nova)	WLE1213_DC800kw	Certified	November 27, 2025		wolun_new_energy	wle1213_dc800kw	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	V105.1.25.10	No	DC	CCS2 Cable	Optional	No	Yes	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
XCharge Europe GmbH	select	Certified	March 22, 2024		xcharge	select	Direct connection	0	OCPP JSON 1.6	SIM, WIFI,LAN	23082301	Not Tested	AC	T2 Socket	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
XCharge Europe GmbH	CSEU	Certified	October 17, 2023		xcharge	cseu	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V2.6.85_CSEU_OCPP_STA_230920	No	DC	CCS2 Cable	Yes	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
XCharge Europe GmbH	CSEU	Certified	October 17, 2023		xcharge	cseu	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V1.0.0_CSEU_OCPP_STA_240920	No	DC	CCS2 Cable	No	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
XCharge Europe GmbH	Nano AC-C22EU	Certified	September 8, 2025		xcharge	c22eu	Direct connection	0	OCPP JSON 1.6	LAN/WIFI	v00.01.00	Not Tested	AC	T2 Socket	Yes	No	No	Yes	Yes	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
xcharger.com.pl	dc12eu	Certified	May 1, 2026		xcharger	dc12eu	Direct connection	0	OCPP JSON 1.6	LAN	4.4.0	Not Tested	DC	T2 Cable	Yes	No	No	Yes	Yes	Yes		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Zaptec	Go (Home-Cloud connection)	Certified	June 20, 2025		zaptec	go_home	Proxy Connection	0	OCPP JSON 1.6	Pub SIM, LAN	2.4.2.4	Not Tested	AC	T2 Socket	No	No	No	No	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Zaptec	Go (Native OCPP-Direct connection)	Certified	June 20, 2025		zaptec	go_native	Direct connection	0	OCPP JSON 1.6	Pub SIM, LAN	2.4.2.4	Not Tested	AC	T2 Socket	No	No	No	Yes	Yes	Not tested	Diagnostics can be requested from the manufacturer.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Zaptec	Go 2 (Home-Cloud connection)	Certified	July 1, 2025		zaptec	go2_home_limited	Proxy Connection	0	OCPP JSON 1.6	Pub SIM, LAN	3.0.2.1	No	AC	T2 Socket	Yes	No	No	No	No	Not tested	Only for home use. RFID authorise will stay in preparing state.	Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
Zaptec	Chargebridge Pro	Certified	November 14, 2019		zaptec	zapcharger_pro	Direct connection	0	OCPP JSON 1.6	SIM, LAN	Fdkn	Not Tested	AC	T2 Socket	Unknown	No	Yes	Yes	Not tested	Not tested		Please contact your vendor for the proper documentation on how to connect the charger to our platform via OCPP.
ZPUE S.A.	EV-CXXX	Certified	December 1, 2023		zpue	ev_cxxx	Direct connection	0	OCPP JSON 1.6	SIM, LAN	V161023	No	DC	CCS2 Cable	Yes	No	No	No	Yes	Not tested	Not tested	GetDiagnostics and RemoteUpdate are supported through manufacturer own connection with the charger	https://support.lastmileolutions.com/hc/en-us/articles/4405586fcb8a7a/setup-guides/register-charge-points-in-evc-net#step-2-update-charge-point-settings